

UPLAND

63 King Steet, Dartmourk, NS B2V 3R7 +1 902 423 0545 uptimotistudio.co

TITLE

PROPOSED TRAILS (AERIAL VIEW)

CLIENT



CREATED BY

Angharad Wylie

REVIEWED BY

Bruce Mans

APPROVED BY

Bruce Mans

DATE

10/31/2019

NOTES


Proposed Trails:

Nichols Lake Falls Trail

Nichols Lake Trail Phase 1 -Community Centre

Western Common Phase 1

NORTH	
SCALE	L
0 250 m	1:15,000



Western Common Recommended Trail Construction Costs July 20, 2009

Trail construction costs will be determined by topography and drainage conditions along the selected route. The following recommended costs are based on average unit rates from recent experience with trail construction and provided for budget and planning purposes only.

Shared-Use Trail (Motorized Vehicles, max. design speed 50 km/h)

- avg_width 12 feet
- trail surface compacted Type 1 gravel
- route selected to avoid gradients steeper than 15%
- allowance made for design / construction to "off-road vehicle" standards including
- engineering of plan and profile, cut and fill, stabilization of side slopes, subsurface drainage
- no allowance for water / wetland crossings
- recommended unit rate: \$130.00 / lineal foot

Shared-Use Trail (No Motorized Vehicles, max. design speed 20 km/h)

- avg. width 10 feet
- trail surface crusher dust on compacted Type 1 gravel base
- route selected to avoid gradients steeper than 10%
- no allowance for water I wetland crossings
- recommended unit rate: \$40.00 / lineal foot

Barrier-Free Trail

- avg. width 6 feet
- trail surface crusher dust on compacted Type 1 gravel base
- route selected to avoid gradients steeper than 5% (i.e. no ramps, curbs or rails required)
- no allowance for water / wetland crossings
- recommended unit rate: \$25.00 / lineal foot

Back-Country Hiking Trail

- avg. width 24 inches
- trail constructed with natural / site materials
- minimal site disturbance
- allowance included for access to remote locations
- recommended unit rate: \$10.00 / lineal foot

Bridges

- wood deck, steel span with abutments
- recommended unit rate: \$170.00 / square foot

Wetland Crossings

- boardwalk on piles
- recommended unit rate: \$100.00 / square foot

