SPECIFICATION.

WORK AT PUBLIC GARDENS

Green House #1

2 new principal rafters 2 x 7 - pipe rabitted for glass
Renew and repair all damaged woodwork
Repair and reset all ventilators
Furnish and hang one new panel door in shed
Remove all glass, paint and reglaxe and furnise all extra
glass required to make a complete job

Green House #2

Renow all woodwork in roof; all stock to be pine of good quality; all work to conform to the present design of roof with principal rafters.

Remove all glass, paint all woodwork and reglaze and furnish all extra glass to make a complete job; repair and renew all damaged ventilation sashes; rehang and set all ventilator fittings.

Principal rafter 2 x 7 - intermediate rafter 2 x 5
Sash bars 2 x 2- purlins 2 x 6 - ridge 2 x 8 all of good quality
pine free from large loose knots, shakes or other
damaging imperfections.

Renew all damaged sash bars (vertical (from south end as at present with same size stock and hang doors; finish with all moldings, etx.

Paint all woodwork two coats with lead and oil paint

Pavilion South Park Street

Rinish and hang one new door " " two " circular top doors

Repair two sashes
Rebuild one part of roof now down. The balance of roof over pavilion should be rebuilt or taken down as it is all rotten.

Claze two doors with obscure glass
Claze ventilator sashes
Claze two sashes
Repair plumbing
Furnish and lay new roofing where damaged
Paint all new work

Lodge

5 new sashes and repair 3 sashes
Reglaze all broken glass in windows and doors
2 new doors with glass panels
New outside steps and make any necessary carpentery repairs
Paint all new work

Band Stand

Repair ceiling where damaged Repair all broken music stands Paint all new work

Digital copy of 102-7-1918-06-25 provided by Halifax Municipal Archives